

AD-A087 540

NEW JERSEY DEPT OF ENVIRONMENTAL PROTECTION TRENTON
NATIONAL DAM SAFETY PROGRAM. FOXS LAKE DAM (NJ00342), PASSAIC R--ETC(U)
JAN 80 W A GUINAN


F/G 13/13

DACW61-79-C-0011


NL

UNCLASSIFIED

1 of 2
AD-A087 540



LEVEL II



ADA 087540

PASSAIC RIVER BASIN
FOXES BROOK, MORRIS COUNTY
NEW JERSEY

FOXES LAKE DAM

NJ 00342

DTIC
ELECT

AUG 6 1980

S

D

D

**PHASE 1 INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM**

THIS DOCUMENT IS BEST QUALITY PRACTICABLE.
IT MAY BE SUBJECT TO DDC CONTAINED A
SIGNIFICANT NUMBER OF PAGES WHICH DO NOT
REPRODUCE FULLY.



**APPROVED FOR PUBLIC RELEASE
DISTRIBUTION UNLIMITED.**

DEPARTMENT OF THE ARMY

Philadelphia District
Corps of Engineers
Philadelphia, Pennsylvania

80 8 4 085

**JANUARY 1980
APPROVED FOR PUBLIC RELEASE
DISTRIBUTION UNLIMITED.**

DDC FILE COPY

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER NJ00342	2. GOVT ACCESSION NO. AD-A087540	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Inspection Report National Dam Safety Program Foxs Lake Dam NJ00342 Morris County, New Jersey		5. TYPE OF REPORT & PERIOD COVERED FINAL
7. AUTHOR(s) WARREN A. GUINAN		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS Anderson-Nichols 6 London Rd. Concord, N.H. 03301		8. CONTRACT OR GRANT NUMBER(s) DACW61-79-C-0011 ✓
11. CONTROLLING OFFICE NAME AND ADDRESS NJ Department of Environmental Protection ✓ Division of Water Resources P.O. Box CN029 Trenton, NJ 08625		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) U.S. Army Engineer District, Philadelphia Custom House, 2d & Chestnut Streets Philadelphia, PA 19106		12. REPORT DATE Jan. 1980
		13. NUMBER OF PAGES 87
		15. SECURITY CLASS. (of this report) Unclassified
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited.		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		Accession For NTIS GRA&I DDC TAB Unannounced Justification By Distribution/ Availability Codes Dist Avail and/or A special
18. SUPPLEMENTARY NOTES Copies are obtainable from National Technical Information Service, Springfield, Virginia 22151.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dams National Dam Safety Program Embankments Foxs Lake Dam, New Jersey Visual Inspection Erosion Structural Analysis Riprap		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report cites results of a technical investigation as to the dam's adequacy. The inspection and evaluation of the dam is as prescribed by the National Dam Inspection Act, Public Law 92-367. The technical investigation includes visual inspection, review of available design and construction records, and preliminary structural and hydraulic and hydrologic calculations, as applicable. An assessment of the dam's general condition is included in the report.		

DD FORM 1 JAN 73 1473 EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

6) National Dam Safety Program.
Foxs Lake Dam (NJ00342), Passaic River
Easin, Foxs Brook, Morris County,
New Jersey. Phase 1 Inspection Report.

9) Final reptos / 10) Wicken A. / Gidara

11) Jan 18

15) DAZW61-77-C-0011

15) 7/1/11

NOTICE

THIS DOCUMENT HAS BEEN REPRODUCED
FROM THE BEST COPY FURNISHED BY
THE SPONSORING AGENCY. ALTHOUGH
IT IS RECOGNIZED THAT CERTAIN POR-
TIONS ARE ILLEGIBLE, IT IS BEING
RELEASED IN THE INTEREST OF MAKING
AVAILABLE AS MUCH INFORMATION AS
POSSIBLE.

417911 DK



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
CUSTOM HOUSE-2 D & CHESTNUT STREETS
PHILADELPHIA, PENNSYLVANIA 19106

IN REPLY REFER TO
NAPEN-N

29 JUL 1980

Honorable Brendan T. Byrne
Governor of New Jersey
Trenton, New Jersey 08621

Dear Governor Byrne:

Inclosed is the Phase I Inspection Report for Foxs Lake Dam in Morris County, New Jersey which has been prepared under authorization of the Dam Inspection Act, Public Law 92-367. A brief assessment of the dam's condition is given in the front of the report.

Based on visual inspection, available records, calculations and past operational performance, Foxs Lake Dam, initially listed as a high hazard potential structure, but reduced to a significant hazard potential structure as a result of this inspection, is judged to be in fair overall condition. The dam's spillway is considered inadequate because a flow equivalent to six percent of the Spillway Design Flood--SDF - would cause the dam to be overtopped. (The SDF, in this instance, is one half of the Probable Maximum Flood.) To ensure adequacy of the structure, the following actions, as a minimum, are recommended:

a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures, and studies within six months from the date of approval of this report. Within three months of the consultant's findings, remedial measures to ensure spillway adequacy should be initiated.

b. Within six months from the date of approval of this report, engineering studies and analyses should be performed to:

(1) Design or specify and oversee repairs for the erosion that has occurred on the upstream slope and on the west abutment.

(2) Design or specify and oversee the installation of riprap or other erosion protection on the upstream face of the dam.

DTIC
ELECTE
S AUG 6 1980 D
D

NAPEN-N

Honorable Brendan T. Byrne

(3) Design or specify and oversee the establishment of grassy vegetation for erosion protection on the crest of the embankment.

(4) Design or specify and oversee repairs to the eroded, spalled and cracked concrete on the ogee spillway, spillway walls and downstream concrete retaining walls.

(5) Specify and oversee procedures for removing trees from the upstream slope of the dam.

(6) Investigate the cause of the unevenness of the crest and design and implement remedial measures if necessary.

c. Within thirty days from the date of approval of this report, the following remedial actions should be initiated:

(1) Start a program of periodically checking the condition of the dam.

(2) Control trespassing on the dam to reduce erosion.

d. The following remedial actions should be initiated within six months from the date of approval of this report.

(1) Clear trees and brush from either side of the downstream channel for a distance of at least 50 feet downstream of the dam or to the nearest property line, whichever is closer to the dam.

(2) Establish a surveillance program for use during and after periods of heavy rainfall and also a warning program to follow in case of emergency conditions.

(3) Expose and clean out valve boxes to the outlet pipes.

(4) Remove the debris at the downstream toe of the spillway.

e. The following remedial actions should be initiated within one year from the date of the report:

(1) The owner should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam.

(2) The outlet valves should be exercised periodically to ensure proper operation and flush any sediment that has collected in the pipes.

NAPEN-N

Honorable Brendan T. Byrne

A copy of the report is being furnished to Mr. Dirk C. Hofman, New Jersey Department of Environmental Protection, the designated State Office contact for this program. Within five days of the date of this letter, a copy will also be sent to Congressman Courter of the Thirteenth District. Under the provision of the Freedom of Information Act, the inspection report will be subject to release by this office, upon request, five days after the date of this letter.

Additional copies of this report may be obtained from the National Technical Information Services (NTIS), Springfield, Virginia 22161 at a reasonable cost. Please allow four to six weeks from the date of this letter for NTIS to have copies of the report available.

An important aspect of the Dam Inspection Program will be the implementation of the recommendations made as a result of the inspection. We accordingly request that we be advised of proposed actions taken by the State to implement our recommendations.

Sincerely,



1 Incl
As stated

JAMES G. TON
Colonel, Corps of Engineers
District Engineer

Copies furnished:
Mr. Dirk C. Hofman, P.E., Deputy Director
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625

Mr. John O'Dowd, Acting Chief
Bureau of Flood Plain Regulation
Division of Water Resources
N.J. Dept. of Environmental Protection
P.O. Box CN029
Trenton, NJ 08625

FOXES LAKE DAM (NJ00342)

CORPS OF ENGINEERS ASSESSMENT OF GENERAL CONDITIONS

This dam was inspected on 9 November 1979 by Anderson-Nichols & Co., Inc. under contract to the State of New Jersey. The State, under agreement with the U.S. Army Engineer District, Philadelphia, had this inspection performed in accordance with the National Dam Inspection Act, Public Law 92-367.

Foxes Lake Dam, initially listed as a high hazard potential structure, but reduced to a significant hazard potential structure as a result of this inspection, is judged to be in fair overall condition. The dam's spillway is considered inadequate because a flow equivalent to six percent of the Spillway Design Flood--SDF - would cause the dam to be overtopped. (The SDF, in this instance, is one half of the Probable Maximum Flood.) To ensure adequacy of the structure, the following actions, as a minimum, are recommended:

a. The spillway's adequacy should be determined by a qualified professional consultant engaged by the owner using more sophisticated methods, procedures, and studies within six months from the date of approval of this report. Within three months of the consultant's findings, remedial measures to ensure spillway adequacy should be initiated.

b. Within six months from the date of approval of this report, engineering studies and analyses should be performed to:

(1) Design or specify and oversee repairs for the erosion that has occurred on the upstream slope and on the west abutment.

(2) Design or specify and oversee the installation of riprap or other erosion protection on the upstream face of the dam.

(3) Design or specify and oversee the establishment of grassy vegetation for erosion protection on the crest of the embankment.

(4) Design or specify and oversee repairs to the eroded, spalled and cracked concrete on the ogee spillway, spillway walls and downstream concrete retaining walls.

(5) Specify and oversee procedures for removing trees from the upstream slope of the dam.

(6) Investigate the cause of the unevenness of the crest and design and implement remedial measures if necessary.

c. Within thirty days from the date of approval of this report, the following remedial actions should be initiated:

(1) Start a program of periodically checking the condition of the dam.

(2) Control trespassing on the dam to reduce erosion.

d. The following remedial actions should be initiated within six months from the date of approval of this report.

(1) Clear trees and brush from either side of the downstream channel for a distance of at least 50 feet downstream of the dam or to the nearest property line, whichever is closer to the dam.

(2) Establish a surveillance program for use during and after periods of heavy rainfall and also a warning program to follow in case of emergency conditions.

(3) Expose and clean out valve boxes to the outlet pipes.

(4) Remove the debris at the downstream toe of the spillway.

e. The following remedial actions should be initiated within one year from the date of the report:

(1) The owner should develop written operating procedures and a periodic maintenance plan to ensure the safety of the dam.

(2) The outlet valves should be exercised periodically to ensure proper operation and flush any sediment that has collected in the pipes.

APPROVED: 

JAMES G. TON
Colonel, Corps of Engineers
District Engineer

DATE: 6 JUN 80

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

Name of Dam: Foxs Lake Dam
Identification No.: FED ID No. NJ00342
State Located: New Jersey
County Located: Morris
Stream: Foxs Brook
River Basin: Passaic
Date of Inspection: November 9, 1979

ASSESSMENT OF GENERAL CONDITIONS

Foxs Lake Dam (commonly known as Park Lakes Dam) is about 55 years old and in fair overall condition. It is small in size and is classified as Significant Hazard. Erosion of the upstream face of the dam embankment has occurred at the west side of the principal spillway structure, leaving the short training wall there undermined and largely non-functional. Some erosion has occurred along the upstream face of the dam embankment east of the principal spillway. There are a few trees growing on the upstream face of the embankment. The concrete principal spillway structure itself is in good overall condition. Some cracking of the concrete was observed and spalling of concrete is generally limited to portions of the structure close to the normal water line. The crest of the dam has a generally uneven surface and is practically void of vegetation. The twin outlet pipes that protrude from the downstream face of the principal spillway structure are in good condition, exhibiting only minor surface rust. The spillway is capable of passing less than 5% of the half-PMF and is inadequate.

We recommend that the owner retain the services of a professional engineer, qualified in the design and inspection of dams, to accomplish the following in the near future: specify and oversee repairs for the erosion that has occurred on the upstream face and at the west spillway abutment; design or specify and oversee the establishment of grassy vegetation for erosion protection of the crest of the embankment; design or specify and oversee repairs to the eroded, spalled and cracked concrete on the ogee spillway, spillway walls, and downstream concrete retaining walls; specify and oversee procedures for removing trees and their root systems from the upstream slope of the dam; further evaluate the hydrology and hydraulics of the watershed, reservoir, dam, and spillway, and design and implement necessary mitigating measures; and investigate the cause of the unevenness of the crest and design and implement remedial measures if necessary.

We further recommend that as a part of operating and maintenance procedures, the owner check the condition of the dam periodically and control trespassing on the dam to reduce erosion. This should commence immediately. In the near future, the owner should: clear brush and trees from either side of the downstream channel for a distance of at least 50 feet downstream of the dam, or the the nearest property line, whichever is closer to the dam; establish a surveillance program for use during and after periods of heavy rainfall, and also a warning program to follow in case of emergency conditions; exercise the outlet valves periodically to insure proper operation

and flush any sediment that has collected in the pipes; expose and clean out valve boxes to the outlet pipes; remove the debris at the downstream toe of the spillway. Within one year from the date of approval of this report, the owner should develop written operating procedures and a periodic maintenance plan to insure the safety of the dam.

ANDERSON-NICHOLS & CO., INC.

Warren A. Guinan

Warren A. Guinan
Project Manager
New Jersey No. 16848



9 NOV 1979

OVERVIEW

FOXES LAKE DAM

CONTENTS

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY REPORT
FOXES LAKE DAM N.J. NO. 25-49 FED ID NO. NJ00342

	<u>Page</u>
SECTION 1 PROJECT INFORMATION	
1.1 <u>General</u>	1
1.2 <u>Project Description</u>	1
1.3 <u>Pertinent Data</u>	2
SECTION 2 ENGINEERING DATA	
2.1 <u>Design</u>	5
2.2 <u>Construction</u>	5
2.3 <u>Operation</u>	5
2.4 <u>Evaluation</u>	5
SECTION 3 VISUAL INSPECTION	6
SECTION 4 OPERATIONAL PROCEDURES	
4.1 <u>Procedures</u>	7
4.2 <u>Maintenance of Dam</u>	7
4.3 <u>Maintenance of Operating Facilities</u>	7
4.4 <u>Warning System</u>	7
4.5 <u>Evaluation of Operational Adequacy</u>	7
SECTION 5 HYDRAULIC/HYDROLOGIC	8
SECTION 6 STRUCTURAL STABILITY .	9
SECTION 7 ASSESSMENT, RECOMMENDATIONS/REMEDIAL MEASURES	
7.1 <u>Assessment</u>	10
7.2 <u>Recommendations/Alternative Measures</u>	10
FIGURES	
1. Essential Project Features	
2. Essential Project Features	
3. Location Map	
APPENDICES	
1. Engineering and Experience Data	
2. Check List Visual Inspection	
3. Photographs	
4. Hydrologic Computations	
5. References	

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the Spillway Test Flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. The test flood provides a measure of relative spillway capacity and serves as an aid in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY INSPECTION PROGRAM
FOXES LAKE DAM
U.S. #NJ00342-N.J. #25-49

SECTION 1
PROJECT INFORMATION

1.1 General

a. Authority. Authority to perform the Phase I Safety Inspection of Foxes Lake Dam (commonly known as Park Lakes Dam) was received from the State of New Jersey, Department of Environmental Protection, Division of Water Resources by letter dated 26 October, 1979 under Contract No. FPM-39 dated 28 June 1978. This Authority was given pursuant to the National Dam Inspection Act, Public Law 92-367 and by agreement between the State and the U.S. Army Engineers District, Philadelphia. The inspection discussed herein was performed by Anderson-Nichols & Company, Inc. on 9 November 1979.

b. Purpose. The purpose of the Phase I Investigation is to develop an assessment of the general conditions with respect to the safety of Foxes Lake Dam and appurtenances based upon available data and visual inspection, and determine any need for emergency measures and conclude if additional studies, investigations, and analyses are necessary and warranted.

1.2 Project Description

a. Description of Dam and Appurtenances. Foxes Lake Dam is a 19-foot high, 160-foot long earthfill and concrete dam. A 12-foot wide, concrete, ogee principal spillway is located near the center of the earthen dam embankment and is covered by a concrete deck, the top of which is approximately level with the 30-foot wide dam embankment crest. The spillway section sits between two 1-foot thick concrete walls which are approximately parallel to the flow through the spillway. These walls intersect the 1-foot thick wingwalls that form the downstream face of the spillway structure at 90° angles. Two 16-inch diameter cast iron outlet pipes protrude from this concrete face, each located about 10 feet from the centerline of flow through the principal spillway. The upstream face of the dam embankment section is grass-covered earth, sloping at about 6H:1V, intermittently protected with poorly preserved riprap. The crest of the embankment section is mostly hardpacked sand and gravel with some grass. A 4-foot high chain link fence runs along most of the upstream edge of the crest, while a 6-foot high chain link fence is located on the downstream edge of the crest. Both fences also cross the concrete principal spillway cap. The downstream face of the embankment section is rocky, tree covered natural ground, the slope of which is about 2H:1V. Essential features of the dam are given in Figures 1 & 2.

b. Location. Foxs Lake Dam is located in Morris County, New Jersey, on Foxs Brook, a tributary to the Rockaway River in the Borough of Rockaway. The dam is shown on the U.S.G.S. Quadrangle, Dover, New Jersey, with coordinates of approximately N74° 31.0' W40° 54.3'. A location map has been included as Figure 3.

c. Size Classification. Foxs Lake Dam is classified as "small" on the basis of storage at the dam crest of 97 acre-feet, which is less than 1,000 acre-feet, but more than 50 acre-feet, and on the basis of its structural height of 22 feet, which is less than 40 feet, in accordance with criteria given in Recommended Guidelines for Safety Inspection of Dams.

d. Hazard Classification. Foxs Lake Dam is located in a residential area. Visual inspection of the downstream area revealed two inhabited structures located about 7 feet above Foxs Brook. It is unlikely that flood stages resulting from a breach of the dam would reach the first floor sills of these structures. Damage could be appreciable but not excessive. A frequently traveled residential street spans Foxs Brook about 1400 feet downstream of the dam and could be significantly damaged by flooding associated with a breach of the dam. Because the dam is located in a populated area, loss of a few lives could be possible should the dam fail. Accordingly, Foxs Lake Dam is classified as Significant Hazard based on the criteria set forth in the Recommended Guidelines for Safety Inspection of Dams.

e. Ownership. The dam is owned by the Borough of Rockaway, 2 East Main Street, Rockaway, New Jersey, 07866. Phone: (201) 627-2000. Mr. Graner of the Public Works Department was contacted for information.

f. Purpose of Dam. The dam is used to provide recreation.

g. Design and Construction History. No information was disclosed regarding the design and construction of the original dam.

h. Normal Operational Procedures. According to Mr. Graner, the water level of Foxs Lake is drawn down "a couple of feet" each June to allow placement of sand on the beaches. No other formal operational procedures are currently in use.

i. Site Geology. No site specific geologic information (such as borings) was available at the time the dam was inspected. Information derived from a report entitled "Engineering Geology of the Northeast Corridor, Washington, DC to Boston, MA" and the Geologic Map of New Jersey (Lewis and Kummel, 1912) indicates that soils within the immediate site area consist of till grading laterally to sand and gravel. These soils form a nearly continuous band which is interpreted to be the end moraine for the last continental glaciation. Although no outcrops were observed during inspection of this dam, the previously mentioned reports indicate that the underlying bedrock consists of granitoid gneiss with associated migmatite, granulite, amphibolite, and granitic rocks of Precambrian age.

1.3 Pertinent Data

a. Drainage Area

1.2 square miles

b. Discharge at Damsite (cfs)

Maximum flood at damsite - unknown

Ungated (total) spillway capacity at maximum pool elevation-138

Low-level outlet (if operable) - 37

c. Elevation (ft. above NGVD)

Top of dam - 615.7 (low point in crest)

Recreation pool - 613.0

Spillway crest - 613.0

Streambed at centerline of dam - 596.5 (downstream)

- 610.0 (upstream)

Maximum tailwater (estimated) - 601

d. Reservoir Length (feet)

Maximum pool - 1370

Recreation pool - 1300

e. Storage (acre-feet)

Recreation pool - 63

Design surcharge ($\frac{1}{2}$ PMF) - 154

Top of dam - 97

f. Reservoir Surface Area (acres)

Top of dam - 14

Recreation pool - 11

Spillway crest - 11

g. Dam

Type - earthfill and concrete

Length - 160 feet

Height - 19 feet (hydraulic)

- 22 feet (structural)

Top width - 30 feet

Side slopes - upstream 6H:1V

- downstream varies - 2H:1V to vertical

Zoning - unknown

Impervious core - unknown

Cutoff - unknown

Grout curtain - unknown

h. Spillway

Type - concrete ogee

Length of weir - 12 feet

Crest elevation - 613.0 feet above NGVD

Gates - none

Upstream channel - Foxs Lake (no approach channel)

Downstream channel - Foxs Brook

i. Regulating Outlets

Type - two 16-inch diameter cast iron pipes, downstream
invert elevation - 606.8 NGVD

Length - 50 feet (estimated)

Access - gate valve installation points approximately
1 foot underground near downstream edge of dam
crest on either side of spillway.

Regulating facilities - one gate valve each pipe, installed
temporarily when drawdown is required.

SECTION 2 ENGINEERING DATA

2.1 Design

No plans, hydraulic or hydrologic data pertinent to Foxs Lake Dam were obtained.

2.2 Construction

No recorded data concerning construction of Foxs Lake Dam were disclosed.

2.3 Operation

No engineering operational data were disclosed.

2.4 Evaluation

a. Availability. A search of the NJDEP files and contact with community officials revealed only a limited amount of recorded information.

b. Adequacy. Because of the limited amount of recorded data available, evaluation of this dam was based solely on visual observations.

c. Validity. Parts of the recorded data retrieved were found to be incorrect based on visual observations.

SECTION 3 VISUAL INSPECTION

3.1 Findings

a. Dam. The upstream slope of the dam shows some erosion at the waterline and there are major erosion channels on the upstream slope next to the west side of the concrete spillway structure and about half-way between the spillway and the west abutment. Most of the riprap on the upstream slope is missing between the spillway and the west abutment and the riprap is in poor condition between the spillway and the east abutment. Some trees are growing on the upstream slope close to the east abutment.

The crest of the dam has a generally uneven surface and is practically bare of vegetation.

Severe erosion of the west abutment has occurred at the end of the concrete wall which retains the downstream side of the embankment. This erosion appears to be associated with trespassing on the abutment.

b. Appurtenant Structures. The downstream face of the ogee spillway is surface eroded approximately 3/4 of an inch exposing the coarse aggregate. The concrete walls on either side of the spillway are also eroded and undermined at the water line. The downstream face of the downstream retaining wall on both sides of the spillway is eroded and spalled on the inclined portion exposing the coarse aggregate. Efflorescence is also showing at many cracks in the surface of the downstream retaining walls.

Corners of the concrete deck above the spillway channel have minor spalling.

c. Reservoir Area. The watershed above the reservoir is moderately sloping; it is partly wooded and partly urbanized. Slopes adjacent to the lake appear to be stable. No evidence of significant sedimentation was observed.

d. Downstream Channel. Three trees have fallen over into the channel downstream of the dam and there are several trees hanging over the channel.

SECTION 4 OPERATIONAL PROCEDURES

4.1 Procedures

No formal operating procedures were disclosed. It was learned that gate valves can be temporarily installed in the twin 16-inch diameter cast iron blowoff lines to facilitate reservoir lowering. The installation points on the lines are about 1 foot underground on either side of the spillway section near the downstream edge of the crest. The water level is lowered each June to allow placement of sand on the beaches for summer recreation.

4.2 Maintenance of Dam

No formal maintenance procedures for the dam were obtained. From the observed condition of the dam, it is apparent that a regular maintenance program has not been followed.

4.3 Maintenance of Operating Facilities

Formal maintenance procedures for the operating facilities do not exist.

4.4 Warning System

No warning system exists for Foxs Lake Dam.

4.5 Evaluation of Operational Adequacy

Because of the lack of operation and maintenance procedures, the remedial measures described in Section 7.2 should be implemented as prescribed.

SECTION 5
HYDROLOGIC/HYDRAULIC

5.1 Evaluation of Features

a. Design Data. An evaluation could not be performed because no data were disclosed.

b. Experience Data. Investigation of the files at the NJDEP and telephone contact with the Borough of Rockaway yielded no data concerning past overtopping of flood heights at Foxs Lake Dam.

c. Visual Observations. Some erosion of the upstream face of the dam embankment at the west side of the principal spillway structure was observed. This has left the short concrete block training wall at the west side of the spillway virtually non-functional. No evidence of overtopping of the dam crest was noted.

d. Overtopping Potential. The hydraulic/hydrologic evaluation for Foxs Lake Dam is based on a selected Spillway Design Flood (SDF) equal to one-half the probable maximum flood (PMF) in accordance with the range of test floods given in the evaluation guidelines, for dams classified as significant hazard and small in size. The PMF was determined by application of the SCS dimensionless unit hydrograph to a 24-hour probable maximum storm of 22.8 inches. Hydrologic computations are given in Appendix 3. The routed half-PMF peak discharge for the subject drainage area is 3,018 cfs.

Water will rise to a depth of 2.7 feet above the spillway crest before overtopping the low point on the dam embankment crest. Under this head the spillway capacity is 138 cfs, which is less than the selected SDF.

Flood routing calculations indicate that Foxs Lake Dam will be overtopped for more than 7 hours to a maximum depth of 3.4 feet under half-PMF conditions. It is estimated that the spillway can pass less than 5 percent of the half-PMF without overtopping the dam; thus, the spillway is considered inadequate.

e. Drawdown Capacity. Assuming that gate valves can be installed in the twin outlet pipelines, it is estimated that the lake can be drained in less than 2 days, assuming no significant inflow. This time period is considered adequate for draining the reservoir in an emergency situation.

SECTION 6 STRUCTURAL STABILITY

6.1 Visual Inspection

Erosion of the upstream slope of the dam and of the west abutment next to the concrete wall which retains the downstream side of the embankment could lead to breaching of the dam if not controlled. The poor condition of the riprap on the upstream slope has contributed to the erosion problem. The lack of vegetation on the crest of the dam makes the crest susceptible to severe erosion if the dam should be overtopped. The unevenness of the crest may be a sign of internal conditions which could adversely affect the stability of the embankment. If trees that are growing on the upstream slope blow over and pull out their roots or if trees die and their roots rot, serious seepage and erosion problems could result. Spalling, erosion, and cracking of the concrete spillway, channel walls and retaining walls could lead to instability of the structure if the deterioration continues.

6.2 Design and Construction Data

No design or construction data pertinent to the structural stability of the dam are available.

6.3 Operating Records

No operating records pertinent to the structural stability of the dam are available.

6.4 Post-Construction Changes

No records of post-construction changes pertinent to the stability of the dam are available.

6.5 Seismic Stability

This dam is in Seismic Zone 1. According to the Recommended Guidelines, dams located in Seismic Zone 1 "may be assumed to present no hazard from earthquake provided static stability conditions are satisfactory and conventional safety margins exist." None of the visual observations made during the inspection are indicative of unstable slopes. However, because no data are available concerning the engineering properties of the embankment and foundation materials for this dam or of the below-ground configuration of the concrete walls in the dam, it is not possible to make an engineering evaluation of the stability of the slopes or the factor of safety under static conditions.

SECTION 7
ASSESSMENT, RECOMMENDATIONS/REMEDIAL MEASURES

7.1 Dam Assessment

a. Condition. Foxs Lake Dam is about 55 years old and is in fair condition.

b. Adequacy of Information. The information available is such that the assessment of the dam must be based primarily on the results of the visual inspection.

c. Urgency. The recommendations in 7.2 a. and 7.2 c. should be implemented by the owner as prescribed below.

d. Necessity for Additional Data/Evaluation. The information available from the visual inspection is adequate to identify the potential problems which are listed in 7.2 a. These problems require the attention of a professional engineer who will have to make additional engineering studies to design or specify remedial measures to rectify the problems. If left unattended, the problems could lead to failure of the structure.

7.2 Recommendations/Remedial Measures

a. Recommendations. The owner should retain a professional engineer qualified in the design and construction of dams to accomplish the following in the near future:

(1) Design or specify and oversee repairs for the erosion that has occurred on the upstream slope and on the west abutment.

(2) Design or specify and oversee the installation of riprap or other erosion protection on the upstream face of the dam.

(3) Design or specify and oversee the establishment of grassy vegetation for erosion protection on the crest of the embankment.

(4) Design or specify and oversee repairs to the eroded, spalled and cracked concrete on the ogee spillway, spillway walls and downstream concrete retaining walls.

(5) Specify and oversee procedures for removing trees and their root systems from the upstream slope of the dam.

(6) Further evaluate the hydrology and hydraulics of the watershed, reservoir, dam and spillway, and design and implement necessary mitigating measures.

(7) Investigate the cause of the unevenness of the crest and design and implement remedial measures if necessary.

b. Operating and Maintenance Procedures: The owner should do the following immediately:

(1) Start a program of periodically checking the condition of the dam.

(2) Control trespassing on the dam to reduce erosion.

The owner should do the following in the near future:

(1) Clear trees and brush from either side of the downstream channel for a distance of at least 50 feet downstream of the dam or to the nearest property line, whichever is closer to the dam.

(2) Establish a surveillance program for use during and after periods of heavy rainfall and also a warning program to follow in case of emergency conditions.


(3) Expose and clean out valve boxes to the outlet pipes.

(4) Remove the debris at the downstream toe of the spillway.

The owner should do the following in the future:

(1) Within one year from the date of approval of this report, the owner should develop written operating procedures and a periodic maintenance plan to insure the safety of the dam.

(2) The outlet valves should be exercised periodically to insure proper operation and flush any sediment that has collected in the pipes.





PLAN

DATA FROM FIELD INSPECTION 11/9/79

Anderson - Nichols & Co., Inc.		U.S. ARMY ENGINEER DIST PHILADELPHIA	
CONCORD		CORPS OF ENGINEERS	
NEW HAMPSHIRE		PHILADELPHIA, PA	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
FOXES LAKE DAM			
FOXES BROOK		NEW JERSEY	
		SCALE: NOT TO SCALE	
		DATE: JANUARY 1980	


FIGURE 1





ROCKS & DEBRIS


SECTION A-A



ELEVATION B-B

DATA FROM FIELD INSPECTION 11/9/79		U.S. ARMY ENGINEER DIST. PHILADELPHIA	
Anderson - Nichols & Co., Inc.		CORPS OF ENGINEERS	
CONCORD		PHILADELPHIA, PA.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
FOXES LAKE DAM			
FOXES BROOK		NEW JERSEY	
		SCALE: NOT TO SCALE	
		DATE: JANUARY 1980	

FIGURE 2



SCALE IN MILES



MAP BASED ON STATE OF NEW JERSEY
OFFICIAL HIGHWAY MAP AND GUIDE.

Anderson-Nichols & Co., Inc.		U.S. ARMY ENGINEER DIST. PHILADELPHIA	
CONCORD		CORPS OF ENGINEERS	
NEW HAMPSHIRE		PHILADELPHIA, PA.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
FOX LAKE DAM			
LOCATION MAP			
FOX LAKE DAM		NEW JERSEY	
		SCALE SEE BAR SCALE	
		DATE JANUARY 1980	

FIGURE 3

APPENDIX 1

ENGINEERING AND EXPERIENCE DATA

FOXS LAKE DAM

Borough of Rockaway

MUNICIPAL BUILDING • 1 EAST MAIN STREET • ROCKAWAY, NEW JERSEY 07866



CHAS. T. NICHOLS
Borough Clerk

July
11th
1968

RECEIVED

JUL 15 '68

DEPT. OF ENVIRONMENT & PLANNING
WATER POLICY AND SUPPLY

Mr. Robert L. Hardman, Chief
Bureau of Water Control
N. J. Dept. of Conservation & Economic Development
Division of Water Policy & Supply
Trenton, N. J. 08625

Dear Mr. Hardman:

re: Rockaway Park Lake
Dam Application No. 93

With regard to your communications of April 26th and July 3rd, 1968, please be advised that the Borough of Rockaway acquired Rockaway Park Lakes, the subject dam and surrounding shore area by Tax Foreclosure on September 12, 1941.

Trusting that this is the information that you desire,
I remain,

Very truly yours,

A handwritten signature in cursive script, reading "Chas. T. Nichols", is written over the typed name.

Chas. T. Nichols
Borough Clerk

P.O. Box 1390
Trenton, N.J. 08625

February 23, 1965

Mr. Martin L. Domb
Rockaway Borough Engineer
Rockaway, New Jersey

Re: Drainage from Proposed Subdivision in
Rockaway Township

Dear Mr. Domb:

This is in response to your letter of December 7 and in confirmation of our telephone conversation of January 12 concerning the jurisdiction of this Division over drainage from one municipality into another, and particularly with respect to the drainage from a proposed 523-home subdivision recently approved in Rockaway Township upstream of a branch of the Rockaway River flowing into and through the Borough Lake known as Fox Pond.

As indicated to you, the jurisdiction of this Division is restricted to the control of encroachments on natural streams, and there is no way in which we can intervene in the development of the subdivision referred to, except with respect to plans which involve fill or other construction in the stream adjacent to the natural stream channel, within the natural and ordinary high water mark. The criteria applied to the investigation for approval of any such plan is based on the probable runoff under conditions of expected future watershed development, which envisions the sort of subdivision that you are now concerned with, during storms of reasonable magnitude, in this instance using a flood frequency of 15 years.

Since our telephone conversation, I have reviewed the files in the matter and find that the comment made by Alfred H. Linden, Assistant Planning Director for the Morris County Planning Board, in his letter to Chairman Keiffer of the Rockaway Planning Board with respect to the safety of Fox's Pond itself is well taken. While we have no drawings descriptive of the dam construction, we find that inspections were made in 1925 and again in 1926, disclosing that a new spillway had been constructed in 1926 without prior approval by this Division as required by statute, R.S. 58b, which relates to the structural safety and stability of dams for the prevention of the hazard to life and property due to failure and release of impounded waters. Inspection disclosed that the spillway was constructed of concrete

February 23, 1965

with a total length of 12 feet and a maximum freeboard of 4.5 feet with an estimated capacity, at the full head of 4.5 feet (dam awash) of about 400 cubic feet per second.

Our design flood at this point, where the total drainage area is 1.3 square miles, is 740 cfs for the 50-year frequency storm which is used in connection with the analysis of dams for safety and stability. While we have no way of knowing that the proposed subdivision development will itself produce a runoff of this magnitude, it is nevertheless indicated, particularly in consideration of Mr. Linden's statement that the top of the earth dam has eroded to the point that only about 20 inches of water over the spillway would result in overtopping of the dam, that the spillway is woefully inadequate, and that the Borough should immediately undertake the necessary steps to reconstruct both the dam and spillway to eliminate this potential safety hazard.

I am enclosing a copy of our booklet entitled, "Information for Applicants for Construction, Alteration or Repair of Dams", and call your attention to page 13, from which you will note that the Fox Lake dam is a Class I dam, and to page 15, specifying that a freeboard of at least one foot is required for Class I dams with small reservoirs of less than 50 acres in area.

Using these criteria, reconstruction should provide for a discharge of 740 cfs at a maximum head over the spillway crest preferably not exceeding 3 feet, even though 3.5 feet would be acceptable.

Reconstruction design and actual work should be carried out under the supervision of a competent licensed professional engineer, and all plans must be approved by this Division before work is begun. We shall be glad to consult with your engineer, at any stage, with respect to preparation of his plans for reconstruction.

Very truly yours,



Robert L. Hardman, P.E.
Chief, Bureau of Water Control

RLH:ec
enc



MORRIS COUNTY PLANNING BOARD

COURT HOUSE MORRISTOWN NEW JERSEY JEPerson 9-4300

December 2, 1964

Mr. Robert C. Keiffer, Chairman
Rockaway Planning Board
Municipal Building
Rockaway, New Jersey

Dear Mr. Keiffer:

Thank you for your letter dated September 22, 1964 concerning the proposed subdivision known as "FLEETWOOD AT ROCKAWAY" located in Rockaway Township.

My letter dated June 17, 1964 to the Rockaway Township Planning Board, we reviewed the preliminary plat of this subdivision. In that letter we discussed the drainage question relative to Fox Pond, and we quote, "However, we would like to point out that, in our opinion, the County bridges would be only a small part of the total drainage impact of this development on Fox's Brook. Although we have not examined the course of the Brook in detail, we believe that along much of its length down to Fox's Pond it has been confined to a channel of very small cross section, with walls, lawns and gardens on either side. We also believe that several footbridges and pipe culverts have been installed across it that will be completely inadequate to handle the torrents of storm water that development will produce.

(In addition, we wonder about the safety of Fox's Pond itself. A field inspection by our staff some five years ago indicated that a rise in the level of the water in the Pond to a height of only about 20 inches over the bottom of the spillway could mean water could go over the top of the earth dam, with possibly very strong damaging results. With children and weather very gradually wearing down the top of the dam (unless it has been paved since), and the possibility of a log or large plank getting stuck across the estimated 12 foot wide spillway, this does not seem like much of a safety margin for a pond of this size. The added peak flows from this development, if not checked within the tract, will certainly tend to increase any such hazard as may exist in this regard.)"

In reply to the September 3rd resolution passed by your Board, we are sorry we must inform you that the County Planning law gives us no power over municipal interests, nor over private property, except to the extent of protecting County drainage requirements.



OFFICE LOCATED AT NEW HANOVER AVENUE AND SAYRE ROAD, MORRISTOWN

Mr. Kieffer

-2-

December 2, 1964

Under the County Planning law we are enabled to advise municipal Board concerning proposed subdivisions and their effect upon the municipality. However, the municipal Board is not obligated to embrace our advisory comments.

We regret that we cannot be of more definite assistance to your Board in this matter.

Very truly yours,

MORRIS COUNTY PLANNING BOARD

M.C. Meadowcroft
M.C. Meadowcroft
Principal Planner

Alfred H. Linden
Alfred H. Linden
Assistant Planning Director

cc: Rockaway Township
Planning Board

MCN:dbc

Report of DAM INSPECTION

ROCKAWAY PARK LAKES—MORRIS COUNTY

On August 5, 1926 in company with Mr. Dean C. Jenkins, engineer, inspection was made of a dam site on the outlet of Fox Lake, tributary of the Rockaway River. The site is at a culvert beneath the Morris Canal. Location 25.3.2.8.8.

The owner is Mr. J. P. O'Conner, representing the Rockaway Park Lakes Company. Mr. O'Conner desires to place the spillway ~~at~~ the southern ~~part of the~~ outlet ^{and at} under the old culvert in order to make it visible from the highroad.

One test pit has been sunk to a depth of 4 feet at the site of the proposed spillway. The material disclosed is a fine brown sand carrying a little clay. Mr. Jenkins was advised that it will be necessary to fill the culvert and carry the water across the top of the old canal "fl" by means of a watertight concrete trough. A cantilever wall design was suggested for the spillway with sheet piling cut-off.

C/H

John N. Brooks,

Hydraulic Engineer.

Frederick, New Jersey.

August 10, 1926.

APPENDIX 2

CHECK LIST

VISUAL INSPECTION

FOXS LAKE DAM

Check List
Visual Inspection
Phase 1

Name Dam Foxs Lake Dam County Morris State NJ Coordinators NJDEP
 Date(s) Inspection Nov. 9, 1979 Weather Partly sunny, mild Temperature 70 degrees F.
 Pool Elevation at Time of Inspection 613.1 NGVD Tailwater at Time of Inspection 598.0 NGVD

Inspection Personnel:

<u>Warren Guinan</u>	<u>Ronald Hirschfeld</u>
<u>Stephen Gilman</u>	
<u>Janusz Czyzowski</u>	

S. Gilman/R. Hirschfeld Recorder

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
SURFACE CRACKS	None observed	
UNUSUAL MOVEMENT OR CRACKING AT OR BEYOND THE TOE	None observed. Downstream face of embankment is retained by vertical concrete wall	
SLOUGHING OR EROSION OF EMBANKMENT AND ABUTMENT SLOPES	Two erosion channels on upstream slope. Minor erosion at waterline	Repair eroded areas on upstream slope and re-establish grassy vegetation.
VERTICAL AND HORIZONTAL ALIGNMENT OF THE CREST	Vertical alignment is not even. Horizontal alignment is good.	
RIPRAP FAILURES	Riprap on upstream slope is in poor to very poor condition.	Provide adequate erosion protection on upstream slope.

EMBANKMENT

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
RAILINGS		
JUNCTION OF EMBANKMENT AND ABUTMENT, SPILLWAY AND DAM	Very severe erosion of upstream slope at right edge of spillway structure. Very severe erosion of concrete wall which retains down- stream face of embankment, apparently caused partly by trespassing	Repair eroded areas. Provide adequate erosion protection. Control trespassing
ANY NOTICEABLE SEEPAGE	None observed	
STAFF GAGE AND RECORDER		
	None observed	
DRAINS		
	None observed	

UNGATED SPILLWAY

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONCRETE WEIR	<p>2 Crests--Both are surface eroded exposing coarse aggregate. Channel walls are eroded and spalled where concrete is in contact with water. D/S toe spalling to a depth of 3". Face of ogee D/S is eroded exposing coarse aggregate.</p> <p>D/S concrete walls-Numerous areas of cracking and spalling. Efflorescence showing at majority of cracks. Worst erosion is at bottom of dam where in contact with water.</p>	<p>Engage an Engineer to design and repair spalled and eroded concrete.</p> <p>Repair spalled and eroded area.</p>

APPROACH CHANNEL

Wide and unobstructed

DISCHARGE CHANNEL

Three trees have fallen over into channel due to erosion of left bank. Other trees overhang channel

Clear trees and brush on either side of channel for some distance downstream from dam.

BRIDGE AND PIERS OVER SPILLWAY

Corners of concrete deck are spalled U/S ends of wall are surface eroded.

Repair spalled and eroded area

OUTLET WORKS

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CRACKING AND SPALLING OF CONCRETE SURFACES IN OUTLET CONDUIT	Not applicable	
INTAKE STRUCTURE	Not visible	
OUTLET PIPE - Two 16" cast iron	Pipes are in good condition, only minor surface rust	No action required
OUTLET CHANNEL	see d/s channel of ungated spillway	
EMERGENCY GATE - two 16" gate valves	Not visible	Expose valve boxes and exercise valves periodically to insure operation and flush out sediment

INSTRUMENTATION

VISUAL EXAMINATION	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
MONUMENTATION/SURVEYS	None observed	
OBSERVATION WELLS	None observed	
WEIRS	None observed	
PIEZOMETERS	None observed	
OTHER	None observed	

RESERVOIR

VISUAL EXAMINATION OF

OBSERVATIONS

REMARKS OR RECOMMENDATIONS

SLOPES

Gently sloping. Homes on shoreline

SEDIMENTATION

No evidence of significant sedimentation observed.

DOWNSTREAM CHANNEL

VISUAL EXAMINATION OF	OBSERVATIONS	REMARKS OR RECOMMENDATIONS
CONDITION (OBSTRUCTIONS, DEBRIS, ETC.)	Rocky bottom, few small trees fallen into channel, others overhanging channel. Small breached dam just upstream of first culvert encountered downstream of dam.	
SLOPES	Narrow channel, low channel banks, moderate to flat sloping overbanks.	
APPROXIMATE NO. OF HOMES AND POPULATION	Two homes--sills are both at least 7 feet above streambed; less than 10 total inhabitants.	

CHECK LIST
ENGINEERING DATA
DESIGN, CONSTRUCTION, OPERATION

ITEM	REMARKS
PLAN OF DAM	None disclosed
REGIONAL VICINITY MAP	Prepared for this report
CONSTRUCTION HISTORY	None
TYPICAL SECTIONS OF DAM	None
HYDROLOGIC/HYDRAULIC DATA	None
OUTLETS - PLAN	None
- DETAILS	None disclosed
- CONSTRAINTS	None disclosed
- DISCHARGE RATINGS	None disclosed
RAINFALL/RESERVOIR RECORDS	None disclosed

ITEM	REMARKS
DESIGN REPORTS	None disclosed
GEOLOGY REPORTS	None disclosed
DESIGN COMPUTATIONS HYDROLOGY & HYDRAULICS DAM STABILITY SEEPAGE STUDIES	None disclosed
MATERIALS INVESTIGATIONS BORING RECORDS LABORATORY FIELD	None disclosed
POST-CONSTRUCTION SURVEYS OF DAM	None disclosed
BORROW SOURCES	Unknown

ITEM	REMARKS
MONITORING SERVICES	None
MODIFICATIONS	None
HIGH POOL RECORDS	None
POST CONSTRUCTION ENGINEERING STUDIES AND REPORTS	None
PRIOR ACCIDENTS OR FAILURE OF DAM DESCRIPTION REPORTS	None
MAINTENANCE OPERATION RECORDS	None

ITEM	REMARKS
SPILLWAY PLAN	Prepared for this report from field inspection data
SECTIONS	
DETAILS	
None	
OPERATING EQUIPMENT	Two 16-inch diameter gate valves
PLANS & DETAILS	
None	

CHECK LIST
HYDROLOGIC AND HYDRAULIC DATA
ENGINEERING DATA

DRAINAGE AREA CHARACTERISTICS: 1.2 sq. miles, residential, hilly
ELEVATION TOP NORMAL POOL (STORAGE CAPACITY): 613.0 NGVD (63ac-ft)
ELEVATION TOP FLOOD CONTROL POOL (STORAGE CAPACITY): not applicable
ELEVATION MAXIMUM DESIGN POOL: 619.1 NGVD (half-PMF)
ELEVATION TOP DAM: low pt. 615.7 NGVD
CREST: restricted flow over concrete

- a. Elevation 613.0 NGVD
- b. Type concrete ogee
- c. Width 31 +
- d. Length 12'
- e. Location Spillover right center of dam
- f. Number and Type of Gates none

OUTLET WORKS: twin low level outlet pipes

- a. Type 16 inch diameter cast iron
each 10' from centerline of flow through principal
- b. Location spillway
- c. Entrance Inverts 607 NGVD
- d. Exit Inverts 606.8 NGVD
- e. Emergency Draindown Facilities none

HYDROMETEOROLOGICAL GAGES: none

- a. Type _____
- b. Location _____
- c. Records _____

MAXIMUM NON-DAMAGING DISCHARGE: 138. CFS

APPENDIX 3

PHOTOGRAPHS

FOXS LAKE DAM



9 NOV 1979

Looking southeast at upstream face of dam embankment
and principal spillway.



9 NOV 1979

Looking south at upstream face of dam embankment
(west end).

FOXS LAKE DAM



9 NOV 1979

Looking east across upstream face at entrance to principal spillway. Note undermined training wall and embankment erosion.



9 NOV 1979


Looking southwest across dam crest.

FOXES LAKE DAM



9 NOV 1979

Looking north at downstream face of principal spillway structure. Note twin blowoff pipes set in concrete at either side of ogee spillway.



9 NOV 1979

Looking northwest through principal spillway opening at upstream reservoir.

FOXS LAKE DAM



9 NOV 1979

Looking north at upstream reservoir from dam crest.



9 NOV 1979

Looking upstream at spalled face of concrete wall
adjacent to principal spillway toe.

FOXS LAKE DAM



9 NOV 1979

Looking downstream at Foxs Brook just below Foxs Lake Dam.



9 NOV 1979

Looking downstream at entrance to first culvert encountered downstream of Foxs Lake Dam.

FOXs LAKE DAM

3-5



9 NOV 1979
Looking downstream at channel just below first culvert.

FOXS LAKE DAM

• • • • •

APPENDIX 4

HYDROLOGIC COMPUTATIONS

FOXS LAKE DAM

• • • • •

JOB NO. 3409-01SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4 IN SCALEHYDROLOGIC COMPUTATIONSDrainage area = 1.2 mi^2

Lake surface area (normal pool) = 11 acres

Evaluation criteria

size: small
hazard: significant

Spillway design flood

Based on size and hazard classification,
the selected spillway design flood will be one
half the probable maximum flood (1/2 PMF).

JOB NO. 3409-01SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4 IN SCALEDETERMINE TIME OF CONCENTRATION, T_C Method 1 *

Estimate velocity

overland flow

reach length = 4600 ft.

$$\text{slope} = \frac{790 - 650}{4600} = 0.03$$

from table, mostly residential ("pastures")
average velocity = 1.5 fps.

channel flow

reach length = 1800 ft (including lake)

$$\text{slope} = \frac{650 - 613}{1800} = 0.02$$

from table, $V_{avg.} = 3 \text{ fps}$

$$T_C = \frac{4600}{1.5} + \frac{1800}{3} = 3667 \text{ sec} \div 61.1 \text{ min.}$$

Method 2 ▽

from group C, runoff curve No. = 77

from nomograph, $T_L = 0.39 \text{ hrs.}$

$$T_C = 1.67 T_L = 1.67(0.39) = 0.65 \text{ hrs} = \underline{39 \text{ min.}}$$

* from "Design of Small Dams", Bureau of Reclamation.

▽ Soil and Water Conservation Engineering, SCS.

JOB NO. 3409-01SQUARES
1/4 IN SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

Method 3*

Overland flow

slope = 0.03 (see Method 1.)


overland flow occurs mostly over a residential area (lawns);

from plot of % of slope vs. velocity,

$$V = 1.3 \text{ fps}$$

Channel flow

estimate channel shape



assume depth of water in channel = 1 ft.

$$A = 4(1) = 4 \text{ ft}^2$$

$$R = \frac{A}{WP} = \frac{4}{2(1) + 4} = 0.67$$

$$V = \frac{1.49}{n} R^{2/3} S^{1/2}$$

$$S = 0.02, R = 0.67, n = 0.045$$

from Manning's nomograph, $V = 3.4 \text{ fps}$

$$T_c = \frac{4600}{1.3} + \frac{1800}{3.4} = 4068 \text{ sec} = \underline{\underline{67.8 \text{ min.}}}$$

* Weston Method (SCS)

JOB NO. 3409-01SQUARES
1/4 IN SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

Method 4 *

$$T_c = 0.83 \left(\frac{NL}{\sqrt{S}} \right)^{0.467}$$

overland flow

$$N = 0.20, S = 0.03, L = 4600 \text{ ft}$$

$$T_{c_{ov}} = 0.83 \left(\frac{0.20(4600)}{\sqrt{0.03}} \right)^{0.467} = 45.6 \text{ min.}$$

channel flow

from Manning's nomograph, $V = 3.4 \text{ fps}$
(see Method 3)


$$T_{c_{ch}} = \frac{1800}{3.4} = 529 \text{ sec} = 8.8 \text{ min.}$$


$$T_c = 45.6 + 8.8 = \underline{54.4 \text{ min.}}$$

$$T_{c_{avg}} = \frac{61 + 39 + 68 + 54}{4} = 55.5 \text{ min} = \underline{0.93 \text{ hr.}}$$

$$T_{LAG} = 0.6 T_c = 0.6(0.93) = 0.56 \text{ hr.}$$

* Kenby Method





JOB NO. 3409-C1

SQUARES
1/4 IN. SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

22

23

24

25

26

27

28

29

30

31

32

33

34

35

36

37

38

DEVELOP RATING CURVE AT DAM

Flow over spillway

Use weir equation, $Q = CLH^{3/2}$, for flow over spillway while a free surface is maintained...

$$C = 2.6^*, H \text{ varies}$$

Use orifice equation, $Q = Ca\sqrt{2gh}$, for pressure flow...

$$C = \left(1 + 0.4\lambda^{0.3} + \frac{0.0045L}{\lambda^{1.25}}\right)^{-1/2}$$

$$\lambda = \frac{3.5(12)}{2(3.5) + 2(12)} = 1.35$$

$$C = \left(1 + 0.4(1.35)^{0.3} + \frac{0.0045(30)}{(1.35)^{1.25}}\right)^{-1/2}$$

$$C = 0.81$$

$$a = 12(3.5) = 42 \text{ ft}^2$$

$$h = \text{water surface} - \text{opening} = \text{W.S.} - 614.8$$

Flow over dam crest

Use weir equation, $Q = CLH^{3/2}$
where $C = 2.4$ and H varies

* from table 5-3, p. 5-40, Everts & King, Handbook of Hydraulics.

† Equation 4-37, p. 4-24, B & K, Handbook of Hydraulics.


Anderson-Nichols & Company, Inc.

Subject FOXES LAKE
 Sheet No. 8 of 16
 Date 5 DEC 74
 Computed GUS
 Checked F.D.D.
JOB NO. 3409-01
 SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
 1/4 IN SCALE


ELEVATION (FT. ABOVE MSL)	SPILLWAY			TOP OF DAM			Q TOTAL
	HEAD (ft)	Q _{weir} (cfs)	Q _{omit.} (cfs)	HEAD* (ft)	LENGTH (ft)	Q (cfs)	
613.0							0
615.7	2.7	138					138
616.2	3.2	179		0.5	23	19	198
616.3	3.3	187		0.6	29	30	217
617.3	4.3	278		1.2	100	280	558
617.4			440	0.8	190	323	763
618.2		503	1.5	258	905	1408
618.7			539	1.4	373	1458	1997
620.0			623	1.9	684	4364	4987
621.0			680	2.7	739	7923	8603

* Average value

9/16



10/16




NO. 31282 IN DISCHARGE IN FT. FROM BOTH WATER. NO. 31282 DISCHARGE.

GRAPH PAPER IN 2000 LINES 11" x 17" MADE IN U.S.A.


11/16



12/16



13/16



Anderson-Nichols & Company, Inc.


Subject FOXES LAKE

Sheet No. 14 of 16
Date 26 DEC 79
Computed GUS
Checked _____

JOB NO. 3409-01

SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4 IN SCALE

OVERTOPPING POTENTIAL



JOB NO. 3409-01SQUARES
1/4 IN SCALE

0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30

DETERMINE "C" FOR LOW LEVEL OUTLET PIPES

Each Pipe:

 $D = \text{diameter} = 16 \text{ in.}$ $n = 0.013$ (from Soil and Water Conservation Engineering*, p. 632) $A_p = \text{area of pipe opening} = 1.4 \text{ ft}^2$ $L_p = \text{length of pipe} = 50 \text{ ft.}$ $K_f = \text{friction loss through pipe}$ $K_L = \text{entrance loss to pipe} = 0.8 \text{ (p. 639*)}$ $C_p = \text{coefficient of discharge (incorporating } A_p \text{ \& 29)}$ $C = \text{coefficient of discharge}$

$$K_f = \frac{5087 n^2}{D^{4/3}} = \frac{5087 (0.013)^2}{(16)^{4/3}} = 0.021$$

$$C_p = A_p \sqrt{\frac{2g}{1 + K_L + K_f L_p}} = 1.4 \sqrt{\frac{64.4}{1 + 0.8 + 0.021(50)}} = 6.66$$

$$C = \frac{C_p}{A / \sqrt{2g}} = \frac{6.66}{1.4 / \sqrt{2g}} = 0.59$$


JOB NO. 3409-01SQUARES 0 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30
1/4 IN. SCALEDRAWDOWN CALCULATIONS

- Assume:
- ① No significant inflow
 - ② Two 16" ϕ outlet pipes are operational
 - ③ $Q_p = C_p H^{1/2} = 6.66 H^{1/2}$
 - ④ $\Delta c - ft/day = 1.9835 \cdot Q_{avg}$
 - ⑤ $Days = \Delta Storage / \Delta c - ft/day$

ELEV. - FT. ABOVE NGVD	STORAGE AC-FT	ΔS AC-FT	H FT.	Q^p CFS	Q_{avg} CFS	$\Delta c - ft$ PER DAY	DAYS
613.0	63		5.5	32			
		11			30	59.5	0.18
612.0	52		4.5	28			
		10			26	51.6	0.19
611.0	42		3.5	24			
		9			22	43.6	0.21
610.0	33		2.5	20			
		8			18	35.7	0.22
609.0	25		1.5	16			
		6			13	25.8	0.23
608.0	19		0.5	10			
		5			5	9.9	0.51
607.5	14		0	0			

$$\Sigma = \underline{\underline{1.54 \text{ DAYS}}}$$

▽ Total Q for two pipes



NATIONAL PROGRAM OF INSPECTION OF
NON-FED. DAMS

FOX'S LAKE DAM

ROCKAWAY TOWNSHIP, NEW JERSEY
REGIONAL VICINITY MAP


JANUARY 1980

DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

ANDERSON-NICHOLS & CO., INC.

CONCORD, N.H.

SCALE IN MILES



MAP BASED ON U.S.G.S. 7.5 MINUTE QUADRANGLE
SHEET. DOVER, N.J., 1954. REVISED, 1970.

HEC-1 OUTPUT

OVERTOPPING ANALYSIS

FOXS LAKE DAM

NOTIFICATION 26 FEB 79

[illegible]

— 3 —

[illegible]

RT DEVELOP INFLOW HYDROGRAPH

11	22.8	113	123.	132
----	------	-----	------	-----

056

I

111

Y0	613.0	615.7	616.2	616.3	617.3	617.9	618.2	618.7	620.	621.
----	-------	-------	-------	-------	-------	-------	-------	-------	------	------

11	SS	0	63	97	104	106	121	123	137	145	170
----	----	---	----	----	-----	-----	-----	-----	-----	-----	-----

606.9	613.0	615.7	616.3	617.3	617.4	618.2	618.7	620.
-------	-------	-------	-------	-------	-------	-------	-------	------

5
\$ 613.00

98	7.6	1	606.9	1	613.0	615.7
----	-----	---	-------	---	-------	-------

[illegible]

RI CHANNEL ROUTING FUD FOLS REACH I

一、二、三、四、五、六、七、八、九、十、十一、十二、十三、十四、十五、十六、十七、十八、十九、二十、二十一、二十二、二十三、二十四、二十五、二十六、二十七、二十八、二十九、三十、三十一、三十二、三十三、三十四、三十五、三十六、三十七、三十八、三十九、四十、四十一、四十二、四十三、四十四、四十五、四十六、四十七、四十八、四十九、五十、五十一、五十二、五十三、五十四、五十五、五十六、五十七、五十八、五十九、六十、六十一、六十二、六十三、六十四、六十五、六十六、六十七、六十八、六十九、七十、七十一、七十二、七十三、七十四、七十五、七十六、七十七、七十八、七十九、八十、八十一、八十二、八十三、八十四、八十五、八十六、八十七、八十八、八十九、九十、九十一、九十二、九十三、九十四、九十五、九十六、九十七、九十八、九十九、一百。

Y7	0.	562.	32.	558.	64.	554.	96.	550.	111.	550.
----	----	------	-----	------	-----	------	-----	------	------	------

1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
27
28
29
30
31
32
33
34
35
36
37
38
39
40
41
42
43
44
45
46
47
48
49
50
51
52
53
54
55
56
57
58
59
60
61
62
63
64
65
66
67
68
69
70
71
72
73
74
75
76
77
78
79
80
81
82
83
84
85
86
87
88
89
90
91
92
93
94
95
96
97
98
99
100
101
102
103
104
105
106
107
108
109
110
111
112
113
114
115
116
117
118
119
120
121
122
123
124
125
126
127
128
129
130
131
132
133
134
135
136
137
138
139
140
141
142
143
144
145
146
147
148
149
150
151
152
153
154
155
156
157
158
159
160
161
162
163
164
165
166
167
168
169
170
171
172
173
174
175
176
177
178
179
180
181
182
183
184
185
186
187
188
189
190
191
192
193
194
195
196
197
198
199
200
201
202
203
204
205
206
207
208
209
210
211
212
213
214
215
216
217
218
219
220
221
222
223
224
225
226
227
228
229
230
231
232
233
234
235
236
237
238
239
240
241
242
243
244
245
246
247
248
249
250
251
252
253
254
255
256
257
258
259
260
261
262
263
264
265
266
267
268
269
270
271
272
273
274
275
276
277
278
279
280
281
282
283
284
285
286
287
288
289
290
291
292
293
294
295
296
297
298
299
300
301
302
303
304
305
306
307
308
309
310
311
312
313
314
315
316
317
318
319
320
321
322
323
324
325
326
327
328
329
330
331
332
333
334
335
336
337
338
339
340
341
342
343
344
345
346
347
348
349
350
351
352
353
354
355
356
357
358
359
360
361
362
363
364
365
366
367
368
369
370
371
372
373
374
375
376
377
378
379
380
381
382
383
384
385
386
387
388
389
390
391
392
393
394
395
396
397
398
399
400
401
402
403
404
405
406
407
408
409
410
411
412
413
414
415
416
417
418
419
420
421
422
423
424
425
426
427
428
429
430
431
432
433
434
435
436
437
438
439
440
441
442
443
444
445
446
447
448
449
450
451
452
453
454
455
456
457
458
459
460
461
462
463
464
465
466
467
468
469
470
471
472
473
474
475
476
477
478
479
480
481
482
483
484
485
486
487
488
489
490
491
492
493
494
495
496
497
498
499
500
501
502
503
504
505
506
507
508
509
510
511
512
513
514
515
516
517
518
519
520
521
522
523
524
525
526
527
528
529
530
531
532
533
534
535
536
537
538
539
540
541
542
543
544
545
546
547
548
549
550
551
552
553
554
555
556
557
558
559
560
561
562
563
564
565
566
567
568
569
570
571
572
573
574
575
576
577
578
579
580
581
582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600
601
602
603
604
605
606
607
608
609
610
611
612
613
614
615
616
617
618
619
620
621
622
623
624
625
626
627
628
629
630
631
632
633
634
635
636
637
638
639
640
641
642
643
644
645
646
647
648
649
650
651
652
653
654
655
656
657
658
659
660
661
662
663
664
665
666
667
668
669
670
671
672
673
674
675
676
677
678
679
680
681
682
683
684
685
686
687
688
689
690
691
692
693
694
695
696
697
698
699
700
701
702
703
704
705
706
707
708
709
710
711
712
713
714
715
716
717
718
719
720
721
722
723
724
725
726
727
728
729
730
731
732
733
734
735
736
737
738
739
740
741
742
743
744
745
746
747
748
749
750
751
752
753
754
755
756
757
758
759
760
761
762
763
764
765
766
767
768
769
770
771
772
773
774
775
776
777
778
779
780
781
782
783
784
785
786
787
788
789
790
791
792
793
794
795
796
797
798
799
800
801
802
803
804
805
806
807
808
809
810
811
812
813
814
815
816
817
818
819
820
821
822
823
824
825
826
827
828
829
830
831
832
833
834
835
836
837
838
839
840
84

— 1 —

	Y6	0.016	0.019	0.016	548.0	560.0	35.0	0.033
--	----	-------	-------	-------	-------	-------	------	-------

2	7	154.	555.	229.	557.5	304.	560.
---	---	------	------	------	-------	------	------

K1 CHANNEL ROUTING MOD FULS REACH 2

11-1

[illegible]

66

1

100

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

	A1
RUNOFF HYDROGRAPH AT	
ROUTE HYDROGRAPH TO	A2
ROUTE HYDROGRAPH TO	A3
ROUTE HYDROGRAPH TO	A4
ROUTE HYDROGRAPH TO	A5
END OF NETWORK	

 FLOOD HYDROGRAPH PACKAGE (PREC-1)
 DAM SAFETY VERSION JULY 1978
 LAST MODIFICATION 26 FEB 79

RUN DATE: 79/12/07.
 TIME: 05.57.17.

PARK LAKES DAM OVERTOPPING ANALYSIS ### GUS SHARRY ANDERSON-NICHOLS ###
 NEW JERSEY DAM NUMBER 25-49 BOROUGH OF ROCKAWAY MORRIS COUNTY
 0.5 MULTIPLE OF PMF FROM 24-HOUR PMF

JOB SPECIFICATION
 NO NHR NMIN IDAY IHR IMIN METRC IPLT IPRT NSTAN
 165 0 10 0 0 0 0 0 0
 JOPER 5 MUT LRPT TRACE
 0 0 0

MULTI-PLAN ANALYSES TO BE PERFORMED
 PLAN= 2 NRATIO= 3 LRATIO= 1
 RTIOS= .10 .25 .50

SUB-AREA RUNOFF COMPUTATION

DEVELOP INFLOW HYDROGRAPH

ISTAG ICOMP IECON ITAPE JPLT JPRY INAME ISTAGE IAUTO
 A1 0 0 0 0 0 1 0 0

HYDROGRAPH DATA

INHYG IUNG TAREA SNAP TRSDA TRSPC RATIO ISNOW ISAME LOCAL
 1 2 1.20 0.00 1.20 .80 0.000 0 1 0

PRECIP DATA

SPFE PMS RC R12 R24 RAR R72 R96
 0.00 22.80 113.00 123.00 132.00 0.00 0.00 0.00

LOSS DATA

LRPT STARR DLTKR RTIOL ERAIN STRKS RTIOK STRTL CNSTL ALSMY RTIMP
 0 0.00 0.00 1.00 0.00 0.00 1.00 1.00 .10 0.00 0.00

UNIT HYDROGRAPH DATA

TC= 0.00 LAG= .50

RECESSION DATA

STRIO= -3.00 GRCSM= 0.00 RTICR= 1.00

UNIT HYDROGRAPH 19 END OF PERIOD ORIGINATES, TC= 0.00 PCURS, LAG= .56 VOL= 1.00 9A.
 1.0. 455. 810. 898. 778. 554. 344. 229. 151. 9A.
 2A. 82. 1P. 12. 6. 3. 1.

END-OF-PERIOD FLOW

MO-DA	HR-MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	MO-DA	HR-MN	PERIOD	RAIN	EXCS	LCSS	COMP Q
1.01	1.10	1	.02	0.00	.02	4.	1.01	13.50	83	.41	.40	.02	1699.
1.01	1.20	2	.02	0.00	.02	4.	1.01	14.00	84	.41	.40	.02	1749.
1.01	1.30	3	.02	0.00	.02	4.	1.01	14.10	85	.52	.50	.02	1795.
1.01	1.40	4	.02	0.00	.02	4.	1.01	14.20	86	.52	.50	.02	1863.
1.01	1.50	5	.02	0.00	.02	4.	1.01	14.30	87	.52	.50	.02	1961.
1.01	1.00	6	.02	0.00	.02	4.	1.01	14.40	88	.52	.50	.02	2063.
1.01	1.10	7	.02	0.00	.02	4.	1.01	14.50	89	.52	.50	.02	2142.
1.01	1.20	8	.02	0.00	.02	4.	1.01	15.00	90	.52	.50	.02	2210.
1.01	1.30	9	.02	0.00	.02	4.	1.01	15.10	91	.47	.45	.02	2242.
1.01	1.40	10	.02	0.00	.02	4.	1.01	15.20	92	.78	.77	.02	2289.
1.01	1.50	11	.02	0.00	.02	4.	1.01	15.30	93	1.41	1.39	.02	2397.
1.01	2.00	12	.02	0.00	.02	4.	1.01	15.40	94	3.52	3.51	.02	3300.
1.01	2.10	13	.02	0.00	.02	4.	1.01	15.50	95	1.02	1.00	.02	4680.
1.01	2.20	14	.02	0.00	.02	4.	1.01	16.00	96	.63	.61	.02	5998.
1.01	2.30	15	.02	0.00	.02	4.	1.01	16.10	97	.48	.46	.02	6303.
1.01	2.40	16	.02	0.00	.02	4.	1.01	16.20	98	.48	.46	.02	5758.
1.01	2.50	17	.02	0.00	.02	4.	1.01	16.30	99	.48	.46	.02	4791.
1.01	3.00	18	.02	0.00	.02	4.	1.01	16.40	100	.48	.46	.02	3881.
1.01	3.10	19	.02	0.00	.02	4.	1.01	16.50	101	.48	.46	.02	3294.
1.01	3.20	20	.02	0.00	.02	4.	1.01	17.00	102	.48	.46	.02	2905.
1.01	3.30	21	.02	0.00	.02	4.	1.01	17.10	103	.38	.36	.02	2633.
1.01	3.40	22	.02	0.00	.02	4.	1.01	17.20	104	.38	.36	.02	2418.
1.01	3.50	23	.02	0.00	.02	4.	1.01	17.30	105	.38	.36	.02	2224.
1.01	4.00	24	.02	0.00	.02	4.	1.01	17.40	106	.38	.36	.02	2059.
1.01	4.10	25	.02	0.00	.02	4.	1.01	17.50	107	.38	.36	.02	1932.
1.01	4.20	26	.02	0.00	.02	4.	1.01	18.00	108	.38	.36	.02	1844.
1.01	4.30	27	.02	0.00	.02	4.	1.01	18.10	109	.03	.01	.02	1741.
1.01	4.40	28	.02	0.00	.02	4.	1.01	18.20	110	.03	.01	.02	1544.
1.01	4.50	29	.02	0.00	.02	4.	1.01	18.30	111	.03	.01	.02	1230.
1.01	5.00	30	.02	0.00	.02	4.	1.01	18.40	112	.03	.01	.02	896.
1.01	5.10	31	.02	0.00	.02	4.	1.01	18.50	113	.03	.01	.02	613.
1.01	5.20	32	.02	0.00	.02	4.	1.01	19.00	114	.03	.01	.02	413.
1.01	5.30	33	.02	0.00	.02	4.	1.01	19.10	115	.03	.01	.02	290.
1.01	5.40	34	.02	0.00	.02	4.	1.01	19.20	116	.03	.01	.02	208.
1.01	5.50	35	.02	0.00	.02	4.	1.01	19.30	117	.03	.01	.02	153.
1.01	6.00	36	.02	0.00	.02	4.	1.01	19.40	118	.03	.01	.02	118.
1.01	6.10	37	.05	0.00	.05	4.	1.01	19.50	119	.03	.01	.02	95.
1.01	6.20	38	.05	0.00	.05	4.	1.01	20.00	120	.03	.01	.02	80.
1.01	6.30	39	.05	0.00	.05	4.	1.01	20.10	121	.03	.01	.02	70.
1.01	6.40	40	.05	0.00	.05	4.	1.01	20.20	122	.03	.01	.02	64.
1.01	6.50	41	.05	0.00	.05	4.	1.01	20.30	123	.03	.01	.02	59.
1.01	7.00	42	.05	0.00	.05	4.	1.01	20.40	124	.03	.01	.02	57.
1.01	7.10	43	.05	.01	.04	5.	1.01	20.50	125	.03	.01	.02	55.
1.01	7.20	44	.05	.03	.02	12.	1.01	21.00	126	.03	.01	.02	54.
1.01	7.30	45	.05	.03	.02	30.	1.01	21.10	127	.03	.01	.02	53.
1.01	7.40	46	.05	.03	.02	58.	1.01	21.20	128	.03	.01	.02	53.
1.01	7.50	47	.05	.03	.02	88.	1.01	21.30	129	.03	.01	.02	53.
1.01	8.00	48	.05	.03	.02	113.	1.01	21.40	130	.03	.01	.02	53.
1.01	8.10	49	.05	.03	.02	130.	1.01	21.50	131	.03	.01	.02	53.
1.01	8.20	50	.05	.03	.02	141.	1.01	22.00	132	.03	.01	.02	53.
1.01	8.30	51	.05	.03	.02	148.	1.01	22.10	133	.03	.01	.02	53.
1.01	8.40	52	.05	.03	.02	153.	1.01	22.20	134	.03	.01	.02	53.
1.01	8.50	53	.05	.03	.02	156.	1.01	22.30	135	.03	.01	.02	53.
1.01	9.00	54	.05	.03	.02	156.	1.01	22.40	136	.03	.01	.02	53.
1.01	9.10	55	.05	.03	.02	159.	1.01	22.50	137	.03	.01	.02	53.
1.01	9.20	56	.05	.03	.02	160.	1.01	23.00	138	.03	.01	.02	53.
1.01	9.30	57	.05	.03	.02	161.	1.01	23.10	139	.03	.01	.02	53.
1.01	9.40	58	.05	.03	.02	161.	1.01	23.20	140	.03	.01	.02	53.

1.01	9.00	60	.05	.03	.02	161.	1.01	23.20	141	.03	.01	.02	53.
1.01	10.00	60	.05	.03	.02	161.	1.01	23.40	142	.03	.01	.02	53.
1.01	10.10	61	.05	.03	.02	161.	1.01	23.50	143	.03	.01	.02	53.
1.01	10.20	62	.05	.03	.02	161.	1.02	0.00	144	.03	.01	.02	53.
1.01	10.30	63	.05	.03	.02	161.	1.02	.10	145	0.00	0.00	0.00	52.
1.01	10.40	64	.05	.03	.02	161.	1.02	.20	146	0.00	0.00	0.00	47.
1.01	10.50	65	.05	.03	.02	161.	1.02	.30	147	0.00	0.00	0.00	30.
1.01	11.00	66	.05	.03	.02	161.	1.02	.40	148	0.00	0.00	0.00	29.
1.01	11.10	67	.05	.03	.02	161.	1.02	.50	149	0.00	0.00	0.00	20.
1.01	11.20	68	.05	.03	.02	161.	1.02	1.00	150	0.00	0.00	0.00	14.
1.01	11.30	69	.05	.03	.02	161.	1.02	1.10	151	0.00	0.00	0.00	11.
1.01	11.40	70	.05	.03	.02	161.	1.02	1.20	152	0.00	0.00	0.00	7.
1.01	11.50	71	.05	.03	.02	161.	1.02	1.30	153	0.00	0.00	0.00	6.
1.01	12.00	72	.05	.03	.02	161.	1.02	1.40	154	0.00	0.00	0.00	5.
1.01	12.10	73	.34	.33	.02	202.	1.02	1.50	155	0.00	0.00	0.00	4.
1.01	12.20	74	.34	.33	.02	335.	1.02	2.00	156	0.00	0.00	0.00	4.
1.01	12.30	75	.34	.33	.02	574.	1.02	2.10	157	0.00	0.00	0.00	4.
1.01	12.40	76	.34	.33	.02	837.	1.02	2.20	158	0.00	0.00	0.00	4.
1.01	12.50	77	.34	.33	.02	1065.	1.02	2.30	159	0.00	0.00	0.00	4.
1.01	13.00	78	.34	.33	.02	1227.	1.02	2.40	160	0.00	0.00	0.00	4.
1.01	13.10	79	.41	.40	.02	1338.	1.02	2.50	161	0.00	0.00	0.00	4.
1.01	13.20	80	.41	.40	.02	1436.	1.02	3.00	162	0.00	0.00	0.00	4.
1.01	13.30	81	.41	.40	.02	1536.	1.02	3.10	163	0.00	0.00	0.00	4.
1.01	13.40	82	.41	.40	.02	1627.	1.02	3.20	164	0.00	0.00	0.00	4.
1.01	13.50	82	.41	.40	.02	1627.	1.02	3.30	165	0.00	0.00	0.00	4.

SUP 24.0R 21.39 2.69 99940.
(612311 543.31 68.31 2829.99)

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
6303. 2504. 693. 606. 99924.

CFS 71. 20. 2830.
INCHES 19.41 21.50 21.52
MM 493.06 546.13 546.53
AC-FT 1242 1375 1376.
1HOUS CU M 1532 1697 1698.

HYDROGRAPH AT STA A1 FOR FLAN 1, RTIC 3

2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.
74.	76.	78.	79.	80.	81.	81.	81.	81.	81.	81.	81.	81.	81.
81.	81.	81.	81.	81.	81.	81.	81.	81.	81.	81.	81.	81.	81.
81.	81.	81.	81.	81.	81.	81.	81.	81.	81.	81.	81.	81.	81.
748.	748.	748.	748.	748.	748.	748.	748.	748.	748.	748.	748.	748.	748.
1121.	1121.	1121.	1121.	1121.	1121.	1121.	1121.	1121.	1121.	1121.	1121.	1121.	1121.
1647.	1647.	1647.	1647.	1647.	1647.	1647.	1647.	1647.	1647.	1647.	1647.	1647.	1647.
615.	615.	615.	615.	615.	615.	615.	615.	615.	615.	615.	615.	615.	615.
35.	35.	35.	35.	35.	35.	35.	35.	35.	35.	35.	35.	35.	35.
27.	27.	27.	27.	27.	27.	27.	27.	27.	27.	27.	27.	27.	27.
27.	27.	27.	27.	27.	27.	27.	27.	27.	27.	27.	27.	27.	27.
5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.	5.
2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.	2.

PEAK 6-HOUR 24-HOUR 72-HOUR TOTAL VOLUME
3151. 1252. 397. 303. 49962.
CFS 49. 35. 10. 10. 1415.
INCHES 9.71 10.75 10.76 10.76 10.76

PM
AC-FT
THOUS CU H

246.53 273.07 273.26 273.26
621. 688. 688. 688.
766. 849. 849. 849.

PLAN 2 SAME AS PLAN 1

HYDROGRAPH ROUTING

ROUTE INFLOW HYDROGRAPH THROUGH RESERVOIR

ISTAG ICOMP IECOM ITAPE JPLT UPRT INAME ISTAGE IAUOTO
A2 1 0 0 0 0 0 1 0 0

ALL PLANS HAVE SAME

ROUTING DATA

QLOSS CLOSS AVG IRES ISAME IOPT IPMP LSTR
0.0 0.000 0.00 1 1 0 0 0

WSTPS WSTDL LAG AMSNK X ISK STORA ISPRAT
1 0 0 0.000 0.000 0.000 63. -1

STAGE	613.00	615.70	616.20	616.30	617.30	617.40	618.20	618.70	620.00	621.00
FLOL	0.00	138.00	198.00	217.00	558.00	763.00	1408.00	1997.00	4987.00	8403.00
CAPACITIVE	0.	63.	97.	104.	106.	121.	123.	137.	145.	170.

ELEVATION= 607. 613. 616. 616. 617. 617. 617. 618. 619. 620.

CREL SPVID COOV EXPV FLEVL COOL CAREA EXPL
613.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0

DAM DATA
TOPEL COOD EXPD DAMUID
615.7 0.0 0.0 0.

END-OF-PERIOD HYDROGRAPH ORCINATES

[illegible]

ROUTING DATA

QLOSS	CLCSS	AVG	IRIS	ISAME	ISPT	ITMP	LSTR
0.0	0.000	0.00	1	1	0	0	0

MSIPS	MSIDL	LAG	AMSKK	X	ISK	STORA	ISPRAT
1	0	0	0.000	0.000	0.000	-1.	0

NORMAL DEPTH CHANNEL ROUTING

QNI(1)	QNI(2)	QNI(3)	FLNVT	ELMAX	RLNTH	SEL
0.00	0.000	0.0500	550.0	562.0	1400.	0.03300

CROSS SECTION COORDINATES--STA,ELEV,STA,ELEV--ETC

0.00	562.00	32.00	558.00	64.00	559.00	96.00	550.00	111.00	550.00
151.00	554.00	191.00	558.00	231.00	562.00				

STORAGE	0.00	14.58	17.31	1.07	20.27	1.95	3.06	4.41	5.98	7.79	9.82	12.09
						23.46	26.88	30.53	34.41	38.52	42.86	47.44

OUTFLOW	0.00	55.25	9975.00	206.87	472.14	871.11	1423.00	2146.02	3200.49	4539.80	6107.69
	7916.24	9975.00	12294.35	14884.18	17754.24	20914.13	24373.33	28141.19	32226.97	36639.80	

STAGE	550.00	550.63	556.32	551.26	557.58	551.89	552.53	553.16	553.79	554.42	555.05	555.68
	556.32	556.95	557.58	558.21	558.84	559.47	560.11	560.74	561.37	562.00		

FLOW	0.00	55.25	9975.00	206.87	472.14	871.11	1423.00	2146.02	3200.49	4539.80	6107.69
	7916.24	9975.00	12294.35	14884.18	17754.24	20914.13	24373.33	28141.19	32226.97	36639.80	

STATION A3, PLAN 2, RTIO 3

[illegible]

.....

HYDROGRAPH ROUTING

CHANNEL ROUTING MOD PULS FIRST CULVERT

ISTAQ	ICOMP	IECON	ITAPE	JUFLT	JPRIT	INAME	ISTAGE	IAUTO
AA	1	0	0	0	1	1	0	0

ALL PLANS HAVE SAME

QLOSS	CLOSS	AVG	IRRES	ISAME	IOPT	IPMP	LSTR
0.0	0.000	0.00	1	1	0	0	0

MSIPS	NSIDL	LAG	AMSKK	X	ISK	STORA	ISPRAT
1	0	0	0.000	0.000	0.000	-1	0

NORMAL DEPTH CHANNEL ROUTING

QNI(1)	QNI(2)	QNI(3)	FLNVT	ELMAX	RLNTH	SEL
0.0160	0.0140	0.0160	548.0	560.0	35	.03300

CROSS SECTION COORDINATES--STAGELEV, STAGELEV--ETC

0.00	560.00	75.00	557.50	150.00	555.00	150.00	558.00	154.00	548.00
154.00	555.00	229.00	557.50	304.00	560.00				

STORAGE	0.00	.02	.00	.03	.01	.01	.01	.01	.01	.02	.02
OUTFLOW	0.00	29.94	82.36	143.68	210.24	279.52	350.70	423.19	496.62	570.75	645.41
STAGE	548.00	548.63	549.26	549.89	550.53	551.16	551.79	552.42	553.05	553.68	554.32
FLOW	645.41	720.50	823.36	904.10	986.88	1071.67	1158.46	1247.25	1338.04	1430.83	1525.62

[illegible][illegible]

MAXIMUM STORAGE = 0.

MAXIMUM STAGE IS 556.9

HYDROGRAPH ROUTING

CHANNEL ROUTING MOD PULS REACH 2

1STAG ICOMP IECON IIAPE JPL1 JPRT INAME ISTAGE IAUO
AS 1 0 0 0 1 0 0

ALL PLANS HAVE SAME

ROUTING DATA
GROSS CLOSS AVG LINES ISAME ITPY ITPHP LSTR
0.0 0.000 0.00 1 0 0 0

NSTPS NSTDL LAG AMSK X TSK STORA ISPRAT
1 0 0 0.000 0.000 -1.0 0

NORMAL DEPTH CHANNEL ROUTING

04(1) 04(2) 04(3) FLNVT ELNVT REINTH SEL
.0350 .0500 .0400 546.0 558.0 300.0 .03300

CROSS SECTION COORDINATES--STA,ELEV,STA,ELEV--ETC
0.00 558.00 315.00 547.50 315.00 546.50 320.00 546.00 325.00 546.50
325.00 547.50 490.00 553.00 640.00 558.00

STORAGE 0.00 .03 .07 .15 .37 .77 1.33 2.05 2.94 3.59
5.21 6.59 8.14 9.85 11.73 13.77 15.98 18.35 20.89 23.59

OUTFLOW 0.00 10.25 50.18 121.04 335.10 810.57 1640.13 2904.82 4678.45 7029.67
10023.21 13720.63 18180.87 23460.67 29614.84 36696.53 44757.38 53847.70 64016.60 75312.10

STAGE 546.00 546.63 547.26 547.89 548.53 549.16 549.79 550.42 551.05 551.68
552.32 552.95 553.58 554.21 554.84 555.47 556.11 556.74 557.37 558.00

FLOW 0.00 10.65 50.18 121.04 335.10 810.57 1640.13 2904.82 4678.45 7029.67
10023.21 13720.63 18180.87 23460.67 29614.84 36696.53 44757.38 53847.70 64016.60 75312.10

A5, PLAN 2, RTIO 3

OUTFLOW

STOR

STAGE

547.2 547.2 547.1 547.1 547.1 547.0 547.0 547.0 546.9

PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFS	3048.	1210.	344.	49553.
CMS	86.	34.	10.	1403.
INCHES		9.38	10.67	10.67
MM		238.32	270.95	271.03
AC-FT		600.	682.	683.
THOUS CU M		740.	842.	842.

MAXIMUM STORAGE = 2.

MAXIMUM STAGE IS 550.5

.....

PEAK FLOW AND STORAGE (END OF PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

RATIOS APPLIED TO FLOWS

OPERATION STATION AREA PLAN. RATIO 1 RATIO 2 RATIO 3
 .10 .25 .50

HYDROGRAPH AT A1 1.20 1 630. 1576. 3151.
 (3.11) (17.85)(44.62)(89.24)(
 2 630. 1576. 3151.
 (17.85)(44.62)(89.24)(

ROUTED TC A2 1.20 1 1103. 1242. 2874.
 (3.11) (31.25)(35.18)(41.38)(
 2 418. 1403. 3018.
 11.827 39.731 85.463

ROUTED TC A3 1.20 1 1084. 1242. 2885.
 (3.11) (30.68)(35.18)(41.71)(
 2 418. 1396. 3035.
 (11.84)(39.54)(85.93)(

ROUTED TC A4 1.20 1 1083. 1243. 2886.
 (3.11) (30.67)(35.19)(41.72)(
 2 418. 1396. 3035.
 (11.84)(39.53)(85.95)(

ROUTED TC A5 1.20 1 1073. 1242. 2884.
 (3.11) (30.45)(35.18)(41.67)(
 2 417. 1394. 3048.
 (11.82)(39.46)(86.31)(

* NOTE: ONLY PLAN 2 APPLIES.

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1									
ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM			
STORAGE		613.00		613.00		615.70			
OUTFLOW		63.		63.		97.			
		0.		0.		138.			
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS		
.10	616.41	.71	108.	1103.	1.00	16.83	15.83		
.25	616.15	.85	103.	1242.	.96	16.50	13.83		
.50	617.79	2.09	130.	2874.	3.10	16.33	13.17		
PLAN 2									
ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM			
STORAGE		613.00		613.00		615.70			
OUTFLOW		63.		63.		97.			
		0.		0.		138.			
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS		
.10	616.89	1.19	115.	418.	3.50	16.67	0.00		
.25	618.19	2.58	137.	1403.	6.17	16.33	0.00		
.50	619.14	3.44	156.	3018.	7.33	16.17	0.00		
PLAN 3									
ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM			
STORAGE		613.00		613.00		615.70			
OUTFLOW		63.		63.		97.			
		0.		0.		138.			
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS		
.10	616.89	1.19	115.	418.	3.50	16.67	0.00		
.25	618.19	2.58	137.	1403.	6.17	16.33	0.00		
.50	619.14	3.44	156.	3018.	7.33	16.17	0.00		
PLAN 4									
ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM			
STORAGE		613.00		613.00		615.70			
OUTFLOW		63.		63.		97.			
		0.		0.		138.			
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS		
.10	616.89	1.19	115.	418.	3.50	16.67	0.00		
.25	618.19	2.58	137.	1403.	6.17	16.33	0.00		
.50	619.14	3.44	156.	3018.	7.33	16.17	0.00		
PLAN 5									
ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM			
STORAGE		613.00		613.00		615.70			
OUTFLOW		63.		63.		97.			
		0.		0.		138.			
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS		
.10	616.89	1.19	115.	418.	3.50	16.67	0.00		
.25	618.19	2.58	137.	1403.	6.17	16.33	0.00		
.50	619.14	3.44	156.	3018.	7.33	16.17	0.00		
PLAN 6									
ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM			
STORAGE		613.00		613.00		615.70			
OUTFLOW		63.		63.		97.			
		0.		0.		138.			
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS		
.10	616.89	1.19	115.	418.	3.50	16.67	0.00		
.25	618.19	2.58	137.	1403.	6.17	16.33	0.00		
.50	619.14	3.44	156.	3018.	7.33	16.17	0.00		
PLAN 7									
ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM			
STORAGE		613.00		613.00		615.70			
OUTFLOW		63.		63.		97.			
		0.		0.		138.			
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS		
.10	616.89	1.19	115.	418.	3.50	16.67	0.00		
.25	618.19	2.58	137.	1403.	6.17	16.33	0.00		
.50	619.14	3.44	156.	3018.	7.33	16.17	0.00		
PLAN 8									
ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM			
STORAGE		613.00		613.00		615.70			
OUTFLOW		63.		63.		97.			
		0.		0.		138.			
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS		
.10	616.89	1.19	115.	418.	3.50	16.67	0.00		
.25	618.19	2.58	137.	1403.	6.17	16.33	0.00		
.50	619.14	3.44	156.	3018.	7.33	16.17	0.00		
PLAN 9									
ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM			
STORAGE		613.00		613.00		615.70			
OUTFLOW		63.		63.		97.			
		0.		0.		138.			
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS		
.10	616.89	1.19	115.	418.	3.50	16.67	0.00		
.25	618.19	2.58	137.	1403.	6.17	16.33	0.00		
.50	619.14	3.44	156.	3018.	7.33	16.17	0.00		
PLAN 10									
ELEVATION		INITIAL VALUE		SPILLWAY CREST		TOP OF DAM			
STORAGE		613.00		613.00		615.70			
OUTFLOW		63.		63.		97.			
		0.		0.		138.			
RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS		
.10	616.89	1.19	115.	418.	3.50	16.67	0.00		
.25	618.19	2.58	137.	1403.	6.17	16.33	0.00		
.50	619.14	3.44	156.	3018.	7.33	16.17	0.00		

NOTE: ONLY PLAN 2 APPLIES.

.50 2 PPK. 556.9 16.33

PLAN 2 STATION A4

RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	418.	552.4	16.67
.25	1396.	556.1	16.33
.50	3035.	556.9	16.33

PLAN 1

STATION A5

RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	1075.	549.4	16.83
.25	1242.	549.5	16.50
.50	2884.	550.4	16.33

PLAN 2

STATION A5

RATIO	MAXIMUM FLOW, CFS	MAXIMUM STAGE, FT	TIME HOURS
.10	417.	548.6	16.67
.25	1394.	549.6	16.33
.50	3048.	550.5	16.33

*NOTE: ONLY PLAN 2 APPLIES.

APPENDIX 5

REFERENCES

FOXS LAKE DAM

.....

AD-A087 540

NEW JERSEY DEPT OF ENVIRONMENTAL PROTECTION TRENTON F/G 13/13
NATIONAL DAM SAFETY PROGRAM. FOXS LAKE DAM (NJ00342), PASSAIC R--ETC(U)
JAN 80 W A GUINAN DACW61-79-C-0011

NL

UNCLASSIFIED

2 of 2

AS 80071-40

END

DATE

FORMED

9-80

DTIC

APPENDIX 5

REFERENCES

FOXS LAKE DAM

1. Brater, E.F., and H.W. King, Handbook of Hydraulics, McGraw-Hill Book Co., New York, Fifth Edition, 1963.
2. Lewis, J.V. and H.B. Kummel (1910-1912) Geologic Map of New Jersey, revised by H.B. Kummel, 1931, and by M.E. Johnson, 1950, New Jersey Department of Conservation and Economic Development Atlas, Sheet 40.
3. New Jersey Department of Environmental Protection Files, "Dams in New Jersey - Reference Data," Dam Number 25-49.
4. Schwab, G.O., R.K. Frevert, T.W. Edminster, and K.K. Barnes Soil and Water Conservation Engineering, the Ferguson Foundation Agricultural Engineering Series, John Wiley & Sons, Inc., New York, New York, 1966, 683 pp.
5. U.S. Department of Commerce, Weather Bureau, "Seasonal Variation of the Probable Maximum Precipitation East of the 105th Meridian for Areas from 10 to 1000 Square Miles and Durations of 6, 12, 24, and 48 Hours", Hydrometeorological Report No. 33, Washington, April 1956.
6. United States Department of the Interior, Geological Survey, 7.5 Minute Series (Topographic) Maps, Scale 1:24,000, Contour Interval 20 Feet: Dover, New Jersey, (1954).
7. United States Department of the Interior, Bureau of Reclamation, Design of Small Dams, U.S. Government Printing Office, Washington, 1977, 816 pp.